

ATA AIRLINES, INC.

AUTOLAND CAPABILITY

PAGE 1 / 1

CHECK BEING PERFORMED: Custom

ZONES: 119 120
A/C NUMBER:
REV. DATE: 02/19/04
FREQUENCY: 1C

W/C NUMBER: 214A2201 DATE:
W/O:
JAC CODE:

PANELS

119BL

MECH INSP

AUTOLAND CAPABILITY

* WORKCARD MUST BE ACCOMPLISHED AT END OF THE "C" CHECK *
* AFTER ALL ITEMS EFFECTING THE AUTOLAND SYSTEM ARE COMPLETE *

XXXXX 1. ENSURE ALL WORK WHICH COULD EFFECT THE AUTOLAND SYSTEM, IS COMPLETE PRIOR TO ACCOMPLISHING STEPS 2 THROUGH 5.

XXXXX 2. ENERGIZE THE MCDP AND DO THE SELF TEST IN ACCORDANCE WITH AMM TASK 22-00-02-712-001.

NOTE: Ensure TMC warning and annunciation lights fully illuminate.

A. Read all flight faults in accordance with AMM TASK 22-00-02-742-006.

XXXXX 3. PERFORM GROUND TEST OF THE AFDS AND THE TMC IN ACCORDANCE WITH AMM TASK 22-00-02-742-011.

XXXXX 4. PERFORM AFDS SYSTEM TEST IN ACCORDANCE WITH AMM TASK 22-10-00-735-040.

XXXXX 5. PERFORM YAW DAMPER SYSTEM TEST IN ACCORDANCE WITH AMM TASK 22-21-00-735-026, 22-21-00-735-145, OR 22-21-00-735-784 (AS CONFIGURED).

*****END OF WORKCARD*****