

ZONES: 200
 A/C NUMBER:
 REV. DATE: 11/01/07
 FREQUENCY: 2C

W/C NUMBER: 321F2713 DATE:

REFERENCES

AMM 27-31-00

MECH INSP

MPD ITEM: 27-082-00

OPERATIONALLY CHECK THE ELEVATOR CONTROL COLUMN OVERRIDE ASSEMBLY

A. References

- (1) AMM TASK 27-31-00-800-801 p201, Elevator Hydraulic System A and B Pressurization
- (2) AMM TASK 27-31-00-840-801 p201, Put the Elevator Hydraulic systems A and B Back to the Condition Before the Pressurization

1. Operational Test - Elevator Control Column Override

A. Procedure

WARNING: MAKE SURE THAT PERSONS AND EQUIPMENT ARE CLEAR OF ALL CONTROL SURFACES BEFORE YOU SUPPLY HYDRAULIC POWER. AILERONS, RUDDERS, ELEVATORS, FLAPS, SPOILERS, SLATS, AND THRUST REVERSERS CAN MOVE QUICKLY WHEN YOU SUPPLY HYDRAULIC POWER. THIS CAN CAUSE INJURY TO PERSONS AND DAMAGE TO EQUIPMENT.

- _____ XXXXX (1) Do this task: Elevator Hydraulic System A or B Pressurization (AMM TASK 27-31-00-800-801 p201).
- _____ XXXXX (2) Do an operational test of the elevator control column override:
- (a) Override Test of the First Officer's Control Column:
 - 1) Push the captain's and first officer's control columns forward.
 - 2) Hold the captain's control column forward (against the forward stop).
 - 3) Pull the first officer's control column aft.
 - 4) Make sure that you can pull the first

A/C NUMBER:

CHECK BEING PERFORMED: Cust

W/C NUMBER: 321F2713 (continued)

MECH: INSP:

officer's control column aft.

- 5) Release the captain's and first officer's control columns go to the neutral position.

(b) Override Test of the Captain's Control Column:

- 1) Push the captain's and first officer's control columns forward.
- 2) Hold the first officer's control column forward (against the forward stop).
- 3) Pull the captain's control column aft.
- 4) Make sure that you can pull the captain's control column aft.
- 5) Release the captain's and first officer's control columns go to the neutral position.

_____ XXXXX

- (3) Do this task: Put the Elevator Hydraulic systems A and B Back to the Condition Before the Pressurization (AMM TASK 27-31-00-840-801 p201).

*****END OF WORKCARD*****